

ADDENDUM NUMBER FOUR

DATE: August 11, 2010

PROJECT TITLE: Photovoltaic Panel Structure and Parking Lot Addition
Shasta Community Health Center
Redding, CA

GENERAL The following revisions supplement the original drawings and shall be included as part of the contract documents. Bidders shall acknowledge receipt of Addendum No. 4 on the final proposal. Failure to acknowledge Addendum No. 4 on the final proposal may disqualify the bidder.

ITEM NO. 4.1: DRAWING SHEET S3.1. Owner to have the option to change the angle of the solar panels. See drawing AD4.1 for different angle options.

ITEM NO. 4.2: CLARIFICATION FOR AD3-3.2. Backfill for the detention basin pipes shall be 2 sack slurry mix over entire structure to obtain maximum compaction to provide a smooth, unyielding surface for asphalt placement. Slurry mix shall be from the bottom of the detention basin pipes to the top of the engineered fill.

Addendum Number 4 contains 2 items and 1 Drawing Attachments.



Ronald Beyer
Architect C-9195
END OF SECTION